
# 15 Years of 2PAD at the Airport Parkway Wastewater Treatment Facility South Burlington, VT

The Northeast Residuals and Biosolids Conference Burlington, Vermont October 25-27, 2017

Presenter
John Reilly, PE

# **Presentation Outline**

- Background
  - Biosolids Management in Chittenden County, VT
  - Biosolids handling at Airport Parkway WWTF
- 15 Years of 2PAD at Airport Parkway WWTF
  - Planning
  - Design
  - Construction
  - Operation
- Reflections on 15 Years of 2PAD



# **Background:**

#### CSWD manages biosolids in Chittenden County, VT

- Final disposition of biosolids managed by Chittenden Solid Waste District (CSWD)
- 18 Member Communities
- 9 Chittenden County WWTF's
- Coordinates with state regulators and commercial partners
- Ensures federal and state disposal requirements are met

# **Background:**

# City of South Burlington Airport Parkway WWTF Basis of Design


| Main Flow           |                                 |
|---------------------|---------------------------------|
| Average Daily Flow  | 3.3 MGD                         |
| Peak Hourly Flow    | 7.92 MGD                        |
| Solids Treatment    |                                 |
| Anaerobic Digestion | Thermophilic -mesophilic (2PAD) |
| Total Mass Loading  | 9,450 lb/day                    |
| Capacity            | 25,332 gpd                      |
| CHP                 | 65 KW microturbine              |
| Dewatering          | Centrifuge                      |















# **Background:**

# Airport Parkway WWTF 2PAD Basis of Design

| Thermophillic Digester    |                    |
|---------------------------|--------------------|
| Operating Temperature     | 55°C (131°F)       |
| Hydraulic Retention Time  | 2.1 Days           |
| Mesophillic Digesters (3) |                    |
| Operating Temperature     | 35°C (95°F)        |
| Hydraulic Retention Time  | 10.5 Days          |
| Digested sludge storage   | 1,000,000 Gallons  |
| СНР                       | 65 KW microturbine |
| Dewatering                | Centrifuge         |







2PAD Upgrade **Construction Complete** Class A Biosolids - VT Sludge Cert. Issued Class A Biosolids VT Sludge Cert. Application 2011 2<sup>nd</sup> 2PAD Facility Designed 2009 - 2010

and Permitted in Vermont

**Final Engineering** Completed **Construction Commences** 

2008 - 2009

**Final Engineering Design** On Hold

2007 - 2008

**Initial Solids Handling Facility Permitting** 

2006

**Facility Plan Initial Permitting** 

2004

Hoyle, Tanner Commences **Airport Parkway WWTF Upgrade Planning** 

2002

**SUEZ Pilot Scale Study** Indianapolis, Indiana WWTF

1997 - 1999

#### 1997-2002:

- SUEZ pilot scale study conducted at Indianapolis WWTF, Indiana to prove 2PAD System
- In 2002, USEPA issues 2PAD Conditional Process to Further Reduce Pathogens (PFRP)

Planning to Modify 2PAD **Control System** 

2017

Conceptual Study & Higher Temperatures

2016

#### 2002

- Solids Handling Problems Identified
  - Poor volatile solids destruction
  - High cost of disposal
- Solids Handling Needs Identified
  - Improved volatile solids destruction
  - Reduced cost of disposal

**Enteric Virus Investigation** & Root Cause Analysis

2015

City Increases 2PAD Feedstock and Utilization

2014

2PAD Upgrade **Construction Complete** 

2013

Class A Biosolids - VT Sludge Cert. Issued

2012

Class A Biosolids VT Sludge Cert. Application

2011

2<sup>nd</sup> 2PAD Facility Designed and Permitted in Vermont

2009 - 2010

**Final Engineering** Completed **Construction Commences** 

2008 - 2009

**Final Engineering Design** On Hold

2007 - 2008

**Initial Solids Handling Facility Permitting** 

2006

**Facility Plan Initial Permitting** 

2004

**Hoyle, Tanner Commences Airport Parkway WWTF Upgrade Planning** 

2002

Planning to Modify 2PAD Control System

2015

2017

Conceptual Study & Higher Temperatures

2016

#### 2004

- Facility Plan
  - Identified Solids Handling by 2PAD
  - Add a single 2.1 day HRT thermophilic digester
  - In lieu of a 4<sup>th</sup> 15 day HRT mesophilic diaester
  - Improve volatile solids destruction
  - Compared to conventional mesophilic digestion.
- Initial Solids Handling Facility Permitting Begins

**Enteric Virus Investigation** & Root Cause Analysis

Feedstock and Utilization

2014

2PAD Upgrade **Construction Complete** 

2013

2012

Class A Biosolids VT Sludge Cert. Application

2011

2<sup>nd</sup> 2PAD Facility Designed and Permitted in Vermont

2009 - 2010

**Final Engineering** Completed **Construction Commences** 

2006

2008 - 2009

**Final Engineering Design** 

2007 - 2008

**Initial Solids Handling Facility Permitting** 

Facility Plan **Initial Permitting** 

2004

Hoyle, Tanner Commences **Airport Parkway WWTF Upgrade Planning** 

2002

**SUEZ Pilot Scale Study** Indianapolis, Indiana WWTF 1997 - 1999

City Increases 2PAD

Class A Biosolids - VT Sludge Cert. Issued

On Hold

Planning to Modify 2PAD Control System

2017

**Conceptual Study** & Higher Temperatures

2016

**Enteric Virus Investigation** & Root Cause Analysis

2014

2015

City Increases 2PAD Feedstock and Utilization

2PAD Upgrade **Construction Complete** 

2013

Class A Biosolids - VT Sludge Cert. Issued

2012

Class A Biosolids VT Sludge Cert. Application

2011

2<sup>nd</sup> 2PAD Facility Designed and Permitted in Vermont

2009 - 2010

**Final Engineering** Completed **Construction Commences** 

2008 - 2009

**Final Engineering Design** On Hold

2007 - 2008

**Initial Solids Handling Facility Permitting** 

2006

**Facility Plan Initial Permitting** 

Initial Solids Handling Facility Permitting

State of VT has permitting authority

State only recognized Title 40: Part 503,

Alternative 1 – time-temperature basis

2PAD does not have Title 40: Part 503,

Alternative 1 – time-temperature basis

National PFRP, by EPA, under Part 503,

2PAD process granted Conditional

Alternative 6 as Class A

2004

Hoyle, Tanner Commences **Airport Parkway WWTF Upgrade Planning** 

for Class A

for Class A

**SUEZ Pilot Scale Study** Indianapolis, Indiana WWTF 1997 - 1999

2006

Planning to Modify 2PAD Control System

2017

**Conceptual Study** & Higher Temperatures

2014

2016

#### 2006

- Initial Solids Handling Facility Permitting (continued)
  - VT did not recognize 2PAD basis for Class A compliance in 2006 for the following reasons:
    - "Unproven technology" (only 4 years since EPA PFRP)
    - VT had various problems at other facilities that tried "new solids treatment technology"
    - Odor concerns

**Enteric Virus Investigation** & Root Cause Analysis

2015

Feedstock and Utilization

2013

Class A Biosolids - VT Sludge Cert. Issued

2012

Class A Biosolids VT Sludge Cert. Application

2<sup>nd</sup> 2PAD Facility Designed and Permitted in Vermont

2009 - 2010

**Final Engineering** Completed **Construction Commences** 

2008 - 2009

**Final Engineering Design** On Hold

**Initial Solids Handling Facility Permitting** 

**Facility Plan Initial Permitting** 

2004

Hoyle, Tanner Commences **Airport Parkway WWTF Upgrade Planning** 

2002

**SUEZ Pilot Scale Study** Indianapolis, Indiana WWTF 1997 - 1999

2PAD Upgrade **Construction Complete** 

City Increases 2PAD

2011

2007 - 2008

Planning to Modify 2PAD Control System

2015

2017

Conceptual Study & Higher Temperatures

2016

#### 2006

- Initial Solids Handling Facility Permitting (continued)
  - City selected to advance with 2PAD construction on the basis of lower capital cost
  - The City intended to operate 2PAD for several years,
  - "Prove" the technology as Class A, then,
  - Reapply to the State for Class A Sludge Certification (Permit)

**Enteric Virus Investigation** & Root Cause Analysis

2014

2PAD Upgrade **Construction Complete** 

2013

Class A Biosolids - VT

2012

Class A Biosolids VT Sludge Cert. Application

2011

2<sup>nd</sup> 2PAD Facility Designed and Permitted in Vermont

2009 - 2010

Completed **Construction Commences** 

2007 - 2008

**Initial Solids Handling Facility Permitting** 

**Facility Plan Initial Permitting** 

2004

Hoyle, Tanner Commences **Airport Parkway WWTF Upgrade Planning** 

2002

**SUEZ Pilot Scale Study** Indianapolis, Indiana WWTF 1997 - 1999

City Increases 2PAD Feedstock and Utilization

Sludge Cert. Issued

**Final Engineering** 

2008 - 2009

**Final Engineering Design** On Hold

Planning to Modify 2PAD **Control System** 

2017

Conceptual Study & Higher Temperatures

2016

#### 2007-2008

Final Engineering Design put on Hold while City resolves internal matter

**Enteric Virus Investigation** & Root Cause Analysis

2015

City Increases 2PAD Feedstock and Utilization

2014

2PAD Upgrade **Construction Complete** 

2013

Class A Biosolids - VT Sludge Cert. Issued

2012

Class A Biosolids VT Sludge Cert. Application

2011

2<sup>nd</sup> 2PAD Facility Designed and Permitted in Vermont

2009 - 2010

**Final Engineering** Completed **Construction Commences** 

2008 - 2009

Final Engineering Design On Hold

2007 - 2008

**Initial Solids Handling Facility Permitting** 

2006

**Facility Plan Initial Permitting** 

2004

Hoyle, Tanner Commences **Airport Parkway WWTF Upgrade Planning** 

2002

Planning to Modify 2PAD **Control System** 

2017

Conceptual Study & Higher Temperatures

2016

**Enteric Virus Investigation** & Root Cause Analysis

2015

City Increases 2PAD Feedstock and Utilization

2014

2PAD Upgrade **Construction Complete** 

2013

Class A Biosolids - VT Sludge Cert. Issued

2012

Class A Biosolids VT Sludge Cert. Application

2011

2<sup>nd</sup> 2PAD Facility Designed and Permitted in Vermont

2009 - 2010

**Final Engineering** Completed **Construction Commences** 

2008 - 2009

**Final Engineering Design** On Hold

2007 - 2008

**Initial Solids Handling Facility Permitting** 

2006

**Facility Plan Initial Permitting** 

Final Engineering completed -

construction commences

2004

Hoyle, Tanner Commences **Airport Parkway WWTF Upgrade Planning** 

2002

**SUEZ Pilot Scale Study** Indianapolis, Indiana WWTF 1997 - 1999

2008-2009



Class A Biosolids VT Sludge Cert. Application

2008 - 2009

2<sup>nd</sup> 2PAD Facility Designed

and Permitted in Vermont

2007 - 2008

**Final Engineering** Completed

**Construction Commences** 

2006

**Final Engineering Design** On Hold

2004

**Initial Solids Handling** 

**Facility Permitting** 

2002

Facility Plan

**Initial Permitting** 


Hoyle, Tanner Commences

**Airport Parkway WWTF** 

**Upgrade Planning** 

Indianapolis, Indiana WWTF 1997 - 1999

**SUEZ Pilot Scale Study** 



Planning to Modify 2PAD **Control System** 

2017

Conceptual Study & Higher Temperatures

2016

#### 2011

- City applies for Class A Biosolids VT Sludge Cert.
  - 9 years of Class A US track record since original EPA PFRP in 2002
  - Brattleboro increased State understanding of 2PAD - 2002 2PAD EPA PFRP Approval

**Enteric Virus Investigation** & Root Cause Analysis

2015

City Increases 2PAD Feedstock and Utilization

2014

2PAD Upgrade **Construction Complete** 

2013

Class A Biosolids - VT Sludge Cert. Issued

2012

Class A Biosolids VT Sludge Cert. Application

2011

2<sup>nd</sup> 2PAD Facility Designed and Permitted in Vermont

2009 - 2010

**Final Engineering** Completed **Construction Commences** 

2008 - 2009

**Final Engineering Design** On Hold

2007 - 2008

**Initial Solids Handling Facility Permitting** 

2006

**Facility Plan Initial Permitting** 

2004

Hoyle, Tanner Commences **Airport Parkway WWTF Upgrade Planning** 

2002

Planning to Modify 2PAD **Control System** 

2017

Conceptual Study & Higher Temperatures

2016

#### 2012

VT issues Class A Biosolids VT Sludge Cert. including monitoring requirements for enteric virus and viable helminth ova that are 3x more stringent than EPA PFRP

**Enteric Virus Investigation** & Root Cause Analysis

2015

City Increases 2PAD Feedstock and Utilization

2014

2PAD Upgrade **Construction Complete** 

2013

Class A Biosolids - VT Sludge Cert. Issued

2012

Class A Biosolids VT Sludge Cert. Application

2011

2<sup>nd</sup> 2PAD Facility Designed and Permitted in Vermont

2009 - 2010

**Final Engineering** Completed **Construction Commences** 

2008 - 2009

**Final Engineering Design** On Hold

2007 - 2008

**Initial Solids Handling Facility Permitting** 

2006

**Facility Plan Initial Permitting** 

2004

**Hoyle, Tanner Commences Airport Parkway WWTF Upgrade Planning** 

2002

Planning to Modify 2PAD **Control System** 

2017

Conceptual Study & Higher Temperatures

2016

#### 2013

- APWWTF 2PAD Upgrade Construction Complete
- City produces Class A biosolids
- CSWD markets final disposition for agronomic utilization

**Enteric Virus Investigation** & Root Cause Analysis

2015

City Increases 2PAD Feedstock and Utilization

2014

2PAD Upgrade **Construction Complete** 

2013

Class A Biosolids - VT Sludge Cert. Issued

2012

Class A Biosolids VT Sludge Cert. Application

2011

2<sup>nd</sup> 2PAD Facility Designed and Permitted in Vermont

2009 - 2010

**Final Engineering** Completed **Construction Commences** 

2008 - 2009

**Final Engineering Design** On Hold

2007 - 2008

**Initial Solids Handling Facility Permitting** 

2006

**Facility Plan Initial Permitting** 

2004

**Hoyle, Tanner Commences Airport Parkway WWTF Upgrade Planning** 

2002

Planning to Modify 2PAD Control System

2017

Conceptual Study & Higher Temperatures

2016

**Enteric Virus Investigation** & Root Cause Analysis

2015

City Increases 2PAD Feedstock and Utilization

2014

2PAD Upgrade **Construction Complete** 

2013

Class A Biosolids - VT Sludge Cert. Issued

2012

Class A Biosolids VT Sludge Cert. Application

2011

2<sup>nd</sup> 2PAD Facility Designed and Permitted in Vermont

2009 - 2010

**Final Engineering** Completed **Construction Commences** 

2008 - 2009

**Final Engineering Design** On Hold

2007 - 2008

**Initial Solids Handling Facility Permitting** 

2006

**Facility Plan Initial Permitting** 

City increases 2PAD feedstock - hauls

City's Bartlett Bay WWTF sludge for

biosolids management costs

2PAD treatment further reducing City

2004

**Hoyle, Tanner Commences Airport Parkway WWTF Upgrade Planning** 

2002

**SUEZ Pilot Scale Study** Indianapolis, Indiana WWTF 1997 - 1999

Planning to Modify 2PAD **Control System** 

2017

Conceptual Study & Higher Temperatures

2014

2016

**Enteric Virus Investigation** & Root Cause Analysis

2015

Feedstock and Utilization

2PAD Upgrade **Construction Complete** 

2013

Class A Biosolids - VT Sludge Cert. Issued

2012

Class A Biosolids VT Sludge Cert. Application

2011

and Permitted in Vermont

**Final Engineering** Completed

2008 - 2009

**Final Engineering Design** On Hold

2007 - 2008

**Initial Solids Handling Facility Permitting** 

2006

**Facility Plan Initial Permitting** 

APWWTF 2PAD subcontractor

of enteric virus in the 2PAD final

Stakeholders immediately

notified and the biosolids

product was held from

biosolid product.

public contact.

laboratory analysis results indicate the

presence of elevated concentrations

Hoyle, Tanner Commences **Airport Parkway WWTF Upgrade Planning** 

2002

**SUEZ Pilot Scale Study** Indianapolis, Indiana WWTF 1997 - 1999

2015

City Increases 2PAD

2<sup>nd</sup> 2PAD Facility Designed

2009 - 2010

**Construction Commences** 

Planning to Modify 2PAD **Control System** 

2015

2017

Conceptual Study & Higher Temperatures

2016

2015 cont.

City and stakeholders concluded an in-depth root cause analysis for the enteric virus "hits" and it was determined by 2 independent labs that a lab error was the cause of the elevated enteric virus concentration rather than the 2PAD process or operations.

City Increases 2PAD Feedstock and Utilization

2014

2PAD Upgrade **Construction Complete** 

2013

**Enteric Virus Investigation** & Root Cause Analysis

Class A Biosolids - VT Sludge Cert. Issued

2012

The 2PAD process was operating as intended and the City had extensive compliance records documenting the process performance.

Class A Biosolids VT Sludge Cert. Application

2011

2<sup>nd</sup> 2PAD Facility Designed and Permitted in Vermont

2009 - 2010

Final Engineering Completed **Construction Commences** 

2008 - 2009

**Final Engineering Design** On Hold

2007 - 2008

**Initial Solids Handling Facility Permitting** 

2006

Facility Plan **Initial Permitting** 

2004

Hoyle, Tanner Commences **Airport Parkway WWTF Upgrade Planning** 

2002

Planning to Modify 2PAD **Control System** 

2015

2017

**Conceptual Study** & Higher Temperatures

2016

#### 2016

- Conceptual Study of 2PAD indicates very little heat loss.
- Conceptual plan developed for new 2PAD control operating mode
- New mode to operate the digester at a higher temperature
- Meets Title 40: Part 503, Alternative 1 – time-temperature Class A

City Increases 2PAD Feedstock and Utilization

2014

2PAD Upgrade **Construction Complete** 

2013

**Enteric Virus Investigation** & Root Cause Analysis

Class A Biosolids - VT Sludge Cert. Issued

2012

Class A Biosolids VT Sludge Cert. Application

2011

2<sup>nd</sup> 2PAD Facility Designed and Permitted in Vermont

2009 - 2010

Completed **Construction Commences** 

**Final Engineering Design** On Hold

2007 - 2008

**Initial Solids Handling Facility Permitting** 

2006

**Facility Plan Initial Permitting** 

2004

Hoyle, Tanner Commences **Airport Parkway WWTF Upgrade Planning** 

2002

**SUEZ Pilot Scale Study** Indianapolis, Indiana WWTF 1997 - 1999

**Final Engineering** 

2008 - 2009

Planning to Modify 2PAD **Control System** 

2015

2017

Conceptual Study & Higher Temperatures

2016

#### 2016 cont.

Same compliance basis as the Brattleboro Facility

The plan: amend the Facility Sludge Cert. for new operating mode and compliance basis and eliminate the monthly enteric virus and viable helminth ova monitoring and lab analysis costs, reducing annual solids

City Increases 2PAD Feedstock and Utilization

2014

2PAD Upgrade **Construction Complete** 

2013

**Enteric Virus Investigation** & Root Cause Analysis

Class A Biosolids - VT Sludge Cert. Issued

2012

Class A Biosolids VT Sludge Cert. Application

2011

handling costs by up to \$25k per year<sup>2nd</sup> 2PAD Facility Designed and Permitted in Vermont

2009 - 2010

**Final Engineering** Completed **Construction Commences** 

2008 - 2009

**Final Engineering Design** On Hold

2007 - 2008

**Initial Solids Handling Facility Permitting** 

2006

**Facility Plan Initial Permitting** 

2004

Hoyle, Tanner Commences **Airport Parkway WWTF Upgrade Planning** 

2002

Planning to Modify 2PAD Control System

2017

Conceptual Study & Higher Temperatures

2014

2016

**Enteric Virus Investigation** & Root Cause Analysis

2015

City Increases 2PAD Feedstock and Utilization

2PAD Upgrade **Construction Complete** 

2013

Class A Biosolids - VT Sludge Cert. Issued

2012

Class A Biosolids VT Sludge Cert. Application

2011

2<sup>nd</sup> 2PAD Facility Designed and Permitted in Vermont

2009 - 2010

**Final Engineering** Completed **Construction Commences** 

2008 - 2009

**Final Engineering Design** On Hold

2007 - 2008

**Initial Solids Handling Facility Permitting** 

2006

**Facility Plan Initial Permitting** 

Ongoing Preliminary Engineering

Planning to modify 2PAD control

for Class A biosolids compliance

system with a time-temperature mode

2004

**Hoyle, Tanner Commences Airport Parkway WWTF Upgrade Planning** 

2002

**SUEZ Pilot Scale Study** Indianapolis, Indiana WWTF 1997 - 1999



### 15 Year Summary of 2PAD in VT

1997-2002 – 5 Years – From 2PAD Pilot Study to EPA PFRP Approval

2009-2010 – 2 Years – Brattleboro Permits modified 2PAD for Class A biosolids production and time-temperature compliance basis

2004-2012 – 8 Years - VT Permits S. Burlington 2PAD Class A including monitoring requirements for enteric virus and viable helminth ova that are 3 x more stringent than the EPA PFRP approval.

2013-2014 – 2 Years of Class A Biosolids Production at Airport Parkway WWTF

2015- Enteric virus exceedance turns out to be a lab error

2016-2017 – Airport Parkway WWTF Plans modified 2PAD control mode to meet time-temperature basis and eliminate COstly enteric virus and helminth ova testing.

### **Airport Parkway WWTF 2PAD Results**

#### 2PAD – Simple Economic Results

Chittenden Solid Waste District manages final Biosolids disposition

Class A biosolids 2013-2017 Land Application: 8,613 wet tons

Avg. 2013-2017 Landfill biosolids disposal rate: \$89.85/wet ton

Avg. 2013-2017 Class A land application rate: \$38.07/wet ton

Avg. 2013-2017 final disposal rate difference: \$51.78/wet ton

2013-2017 simple savings: \$445,981

■ Microturbine electricity produced 2013-2017: 1,000 MWh

Average GMP Power Cost: ~\$0.13/KWh

Simple value of electrical power produced: \$130,000

# 15 Year of 2PAD at Airport Parkway WWTF

# Lessons learned from bringing an advanced solids treatment process to VT

- 1. Advanced treatment processes can have a long time horizon
- 2. Provide immediate response to permit excursions or other concerns
- 3. Secure adequate feedstock quantity and quality
- 4. Cultivate good stakeholder relationships

# **Acknowledgements**

- City of South Burlington
  - Justin Rabidoux, Director of Public Works
  - Chuck Hafter, City Manager (retired)
  - Bob Fischer, Water Quality Superintendent
  - Steve Crosby, Water Quality Superintendent (retired)
  - Robert Baillargeon, Chief Operator
  - Kevin McLaughlin, Operator
- State of Vermont
  - Ernie Kelley
  - Allison Lowry
  - · Catherine Jamieson
- Chittenden Solid Waste District
  - Tom Moreau, General Manager
  - Josh Tyler, Project Manager
- Gene Forbes, PE, formerly with Hoyle, Tanner & Associates, Inc.
- Mike Schramm, PE, Hoyle, Tanner & Associates, Inc.
- Dan Marks, PE, Hoyle, Tanner & Associates, Inc.
- Kirstin DiPietro-Worden, PE, Hoyle, Tanner & Associates, Inc.
- SUEZ (formerly Infilco Degremont and Ondeo Degremont)
- PCC Construction, Inc.

#### Thank You

# Questions?

John D. Reilly, PE jreilly@hoyletanner.com