

NEWEA Biosolids Conference

Schlepping Southington Sludge while Saving Scents

October 2016

Presenting Team

Amy Sowitcky, P.E. Tighe & Bond Project Manager

Austin Weidner, Tighe & Bond Engineer

Agenda

- **Southington Plant**
- **Historical Solids Handling**
 - Changes Needed
 - Options considered
- **Sludge Thickening and Odor Control Project**
 - Project elements
 - Lessons Learned
- **Current Solids Handling**
 - Sludge Thickening
 - Sludge Hauling
- **Future Solids Handling**
 - Low Level Phosphorous Removal Upgrade
 - Impacts

Southington Maintains an Extensive Wastewater System


- 7.4 million gallon per day Water Pollution Control Facility
- Ten pumping stations
- Over 120 miles of sanitary sewers
- Serves over 25,000 residents and businesses



Southington Water Pollution Control Plant



Historic Solid's Management



A Brief History



Problems:

- Additional 450 lb/day Intermediate Solids
- Lost the primary sludge blankets
- Significant Odors from the Primary Clarifiers and Trickling Filters



1980
Last
Major
Upgrade

2012
Digesters
Off-Line

Summer 2013
Odor Issue
Arises

Temporary Solution:


- Permanganate and Hypo Addition
- Stopped Cosettling
- Hauled Sludge more Frequently



2009
Denitrification
Filters Online

Spring 2013
New Permit

Fall 2013
RDT Project
Starts



New Phosphorus Limit and Schedule

- Interim Limit: TP = 0.7 mg/L Immediately
- Future Limit: TP = <0.12 mg/L by 2022

Tighe&Bond

Most Sludge Handling Processes were Off-line and Inefficient

- **Sludge treatment processes**

- *Sludge blending in the primary clarifiers (odorous)*
- *Gravity thickening*
- *Anaerobic digestion & GBT*
- *Dewatering and hauling to MDC*

- **Immediate Needs**

- *Control objectionable odors*
- *Reduce sludge disposal costs*



Sludge Handling and Odor Control Options

- **Sludge treatment options**

- *Continue current sludge disposal practice*

Option 1



Sludge Handling and Odor Control Options

- **Sludge treatment options**

- *Thickener Project*

- *Reuse gravity thickener to store sludges separately*
- *Cover storage tanks*
- *Keep sludges “fresh”*
- *Provide odor control*
- *Thicken to cut volume by 50%*

Option 2



Sludge Handling and Odor Control Options

- **Sludge treatment options**

- *Thickener project **PLUS** rehab digesters and replace process equipment*

Option 3



Sludge Handling and Odor Control Options

	<i>Option 1</i> Continue current sludge disposal practice	<i>Option 2</i> Thickener project only	<i>Option 3</i> Thickener project, rehab digesters, and replace process equip
Capital Cost	\$0	\$5,520,000	\$14,300,000
<i>Annual O&M Cost</i>	<i>\$1,180,000</i>	<i>\$589,000</i>	<i>\$407,000</i>
Net Present Value Cost (for 20 years)	\$21,300,000	\$16,100,000	\$21,700,000
<i>Addresses Immediate Odors</i>	<i>No</i>	<i>Yes</i>	<i>Yes</i>

Sludge Thickening and Odor Control Project



- **Reuse the Gravity Thickener Tanks as aerated storage tanks while waiting for processing through the RDTs**
 - 3 blowers
 - Duckbill valve type aerators
 - Sludge piping
 - Covers
 - Radial odor control system

- **Add sludge feed pumps, thickened pumps and replace truck loading pumps**
 - Flow meters
 - Piping

Sludge Thickening

■ Repurpose the Hypochlorite Room

- *Two 300 gpm RDTs*
- *Booster spray wash pumps*
- *Thickened Pumps*
- *Polymer storage and 2 systems*
- *Carbon odor*
- *Ventilation*
- *Access doors*



STOC: Good News \$\$\$

- *Goal: Under \$4 million – construction \$3,975,000*

*Trucks reduced from 40 plus Monday – Saturday
to 20 Monday through Friday*


- *Operator time*
- *Reduced Sludge Removal Costs:*

- *Truck Hauling*

- *Tipping Fees*


- *Reduces taxed sludge
accepting facilities around CT*

Southington Sludge Hauling Costs



Good News Continues: Scents

- *Remove intermediate and nitrification sludges from the uncovered primary tanks*
 - *Reduced odors*
 - *No overtopping of weirs*
- *Containment and Treatment*
- *Greater flexibility for sludge holding, Processing*
 - *Operators control*



STOC: Polymer versus Solids Content

■ Lessons Learned

- *Sludge & Polymer:*
 - *Polymer selection - Bench scale testing by Parks*
 - *Day 1: Smoothest startup day ever*
 - *Day 2: Gelled, clumped and did not floc*
 - *Consistency: PS, Int. S, Nit. S*
 - *Age of the Sludge*
 - *Aerated sludge*




Thickening

- *Polymer versus Solids Content*
- *How much / what to process*
- *Current sweet spot (PAC addition)*
 - *From 0.4% solids of intermediate and nitrification sludge to 4.7%-6%*
 - *This is added to the former digester, which has straight primary sludge at 2.5%-3%*




A Brief History




Phosphorus Removal Upgrade Project

■ Goals

- *Meet 0.12 mg/L Total Phosphorus Limit*
 - *Complete Construction by 2022 Permit Deadline*
 - *Secure 50% Grant from CT DEEP*
- 
- An architectural drawing showing a cross-section of a building. It includes labels for 'METAL BUILDING' and 'FOUNDATION'. There are also dimensions and structural details indicated by lines and text.

■ Implementation

- *Preselect Ballasted Flocculation Vendor*
- *Determine Impact from Additional Sludge*
- *Phos Sludge Cosettle in Primary Clarifiers*



Sludge Production Estimate

■ Basis of Design

- *Existing Sludge Volume from Observed Data*
- *Vendor guaranteed chemical dosing*
- *Season Permit Season*


	Current Conditions (ADF = 4.5 MGD) ¹			Future Conditions (ADF = 6.04 MGD)		
	AVG	MAX	MIN ²	AVG ³	MAX ⁴	MIN ^{2,5}
Total WPCP Sludge (incl Multipoint) (lbs/day)	6,240	10,457	3,262	8,480	14,210	4,433
Low-level Phos (lbs/day) ^{6,7}	0	0	0	518	805	0
Total (dry lbs/day)	6,240	10,457	3,262	8,997	15,015	4,433
Estimated % Solids of Combined Sludges (with Thickening) ⁸	5%	4%	5.5%	5%	4%	5.5%
Total Sludge Volume (gal)	14,816	31,036	7,041	21,362	44,564	9,568

Additional Sludge & Odor Improvements

- **Convert two digesters to thickened sludge holding tanks**
 - Demo all digester piping
 - New fixed covers
 - New pumped mixing systems
 - Dedicated odor control system for tanks
- **Full Covers on Grit Tanks & Primary Clarifiers**
- **Odor Control System for Headworks and Primary Clarifiers**



A Brief History



Closing

■ Acknowledgements

- Mike Finoia, Town of Southington
- James Grappone, Town of Southington
- Fred Mueller, P.E., Tighe & Bond

■ Discussion & Questions



Amy Sowitcky, P.E.
Tighe & Bond
alsowitcky@tighebond.com
(860) 704-4788

Austin Weidner
Tighe & Bond
adweidner@tighebond.com
(508) 471-9630